

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21669-00-00
Spot: NWSESENW Sec/Twnshp/Rge: 26-13S-30W
2200 feet from N Section Line, 2084 feet from W Section Line
Lease Name: L&M Well #: 4
County: GOVE Total Vertical Depth: 4696 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4627		100 SX
SURF	8.625	340		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/05/2018 10:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: CHUCK TONER Company: COMPANY SERVICING TOOLS Phone: (620) 546-4752

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 500 # gel and 1000 # hulls.
Port collar at 2341' w/450 sx cement.
PBSD 4500' w/CIBP.
Perforations: 4458' - 4466' and 4470' - 4475'.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/05/2018 3:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Whitetail Crude ran in hole with tubing to 4415'. Global rigged to tubing and pumped 1500 # gel followed by 65 sx cement w/300 # hulls mixed in. Pulled tubing to 2350' and pumped 60 sx cement w/150 # hulls mixed in. Pulled tubing to 1708' and pumped 85 sx cement w/300 # hulls mixed in. Pulled tubing to 849' and pumped 75 sx cement w/300 # hulls to circulate cement to pit area. Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 15 sx cement w/200 psi. Shut in pressure 200 psi. Rigged to 8 5/8" surface casing with instant pressure. Backside already cemented.

GPS: 38.89674 -100.62397

Perfs:

Top	Bot	Thru	Comments
4514	4529		
4470	4475		
4458	4466		

Remarks: GLOBAL CEMENTING CO. TICKET # 3257

Plugged through: TBG

District: 04

Signed _____

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

FEB 06 2018

FEB 23 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

INVOICED
MAR 02 2018