

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-081-22101-00-00  
Spot: SESESENW Sec/Twnshp/Rge: 25-28S-31W  
2785 feet from S Section Line, 2919 feet from E Section Line  
Lease Name: GILBERT NICKEL Well #: 1-25(NW)  
County: HASKELL Total Vertical Depth: 5534 feet

Operator License No.: 5316  
Op Name: FALCON EXPLORATION, INC.  
Address: 125 N MARKET STE 1252  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5350		WITH 2 SX CMT
PROD	5.5	5534	2032	WITH 200 SX CMT
SURF	8.625	1829		WITH 550 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/24/2018 10:00 AM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Revd. from: CHUCK TONER Company: FALCON EXPLORATION Phone: (620) 546-4752

Proposed Plugging Method: SET CIBP @ 5350' WITH 2 SX CMT. LOAD 5 1/2" & TEST. PLUG AT 1850' WITH 15 SX GEL & 50 SX CMT. PLUG AT 900' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/24/2018 5:00 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

SET CIBP @ 5350' WITH 2 SX CMT. PRESSURED UP 5 1/2" CASING TO 300# & HELD. 1ST PLUG AT 1862' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 896' WITH 40 SX CMT. 3RD PLUG AT 40' TO SURFACE WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5396	5404		
5390	5404		

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL CEMENTING.

Plugged through: CSG

District: 01

Signed Heith Walsh  
(TECHNICIAN)

RECEIVED  
JAN 29 2018  
KCC DODGE CITY

5A

INVOICED  
MAR 02 2018