



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAR 11 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Dwight J. Wilson of Alpine Oil & Royalty Co. has this date requested permission to plug the following described well:

Mr. Dwight J. Wilson guarantees payment of the plugging fee.

Operator's full Name: Alpine Oil & Royalty Co., Inc.

Complete Address: 800 Bitting Bldg., Wichita, Kansas

Lease Name: Clarence Denbo Well No. # 1

Location: SE SE SW Sec. 26 Twp. 20 Rge. 13 (E) (W)

County Barton Total Depth 3570 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Glenn was instructed to plug the well as follows:

8 5/8" 205' Gwc.

Set bottom plug @ 3280' & dumped 4 sax cement with dump bailer. Pulled pipe. Mudded hole to 205'; set rock bridge; dumped 6 sax cement with dump bailer. Allowed to set over night; bailed hole dry; displaced 20 sax cement. Mud to 40'; set rock bridge; displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

 Conservation Division Agent