

State of Kansas



15-009.05271.0000 FORM - CP-2

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 5 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Claton Hopper of Virginia Drlg. Co., Inc. has this date requested permission to plug the following described well:

Mr. S. A. Murphy guarantees payment of the plugging fee.

Operator's full Name: Virginia Drilling Company, Inc.

Complete Address: 712 Brown Bldg., Wichita, Kansas

Lease Name: Lonnon Well No. # 4

Location: SE NW SE Sec. 25 Twp. 20 Rge. 13 (E) (W)

County Barton Total Depth 3514 Oil Well

Gas Well    Input Well    SWD Well    D & A X    Lost Hole   

Mr. Claton Hopper was instructed to plug the well as follows:

8 5/8" 255' Cwc.

Filled hole with heavy mud to 240'; set plug with 1/4  
sax hulls: displaced 25 sax cement thru drill pipe. Mud  
to 40'; 1/2 sax hulls: plug; displaced 12 sax cement,  
cementing to base of cellar.

Very truly yours,

Don Tramm  
Conservation Division Agent