

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 101-15

LOCATION SE-ME-SW

SEC. 32 TWP. 20 RGE. 13-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Wright

Operator Ben F. Braach Oil Co, Inc. Address #309 Brown Bldg Wichita-Kans.

Field _____ County Barton

Total Depth 3566 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 146 ft - Circulated with cement
5 1/2" casing set at 3523 ft - 100 sacks of cement - Plugged
back to 3500 ft with sand - Pumped 5 sacks of cement
at 3500 ft - Shot off & pulled the 5 1/2" casing - Pumped
in 30 sacks of mud - Plug & 100 sacks of cement
filling hole from 300 ft to the surface with cement.
Remained in by Halliburton -

Pipe Pulling, Inc. Plugging Contractors

PLUGGING
FILE SEC 22 T 20 R 13W
BOOK PAGE 10 LINE 15

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1953
CONSERVATION DIVISION
Wichita, Kansas

C. H. Stough -
District Conservation Agent
Date 6-1-53