

## DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 4-33LOCATION NE-NE-SWSEC. 32 TWP. 20 RGE. 13 WDry Hole  Abandoned Oil Well  Abandoned Gas Well 

I have this date completed supervision of plugging of:

Well No. 1 Lease WrightOperator Ben F. Brack Oil Co Inc. Address 309 Brown Bldg. Wichita Kans.Field \_\_\_\_\_ County BartonTotal Depth 3561 Feet.Plugging Contractor J.M. Casing Pulling Co.Plugging Contractor's License No. 11Address Great Bend Kans.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 $\frac{1}{2}$ " @ 141' C.W.C. Oil string 5 $\frac{1}{2}$ " @ 3546'  
set w/ 75 sk Cem. Casing perforated 3422' filled  
back with sand to 3400' dumped 5 sk Cem.  
shot off and pulled 5 $\frac{1}{2}$ " casing. Pumped in  
20 sk fresh fill mud. Plug and 125 sk Cem  
filling hole and surface. Casing from approx  
375' to base of collar with Cem.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 12 1954

CONSERVATION DIVISION  
Wichita, Kansas  
5-12-54

Darren H. Harner  
District Conservation Agent

Date May 10, 1954