

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 4-32

LOCATION 7w-NE-SW

SEC. 32 TWP. 20 RGE. 13w

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 3 Lease Wright

Operator Ben F. Brack Oil Co Inc. Address 309 Brown Bldg Wichita Ks.

Field \_\_\_\_\_ County Barton

Total Depth 3564 Feet.

Plugging Contractor J M Casing Pulling Co

Plugging Contractor's License No. 11

Address Great Bend Kans.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4" @ 149' c.w.c. Oil string 5 1/2" @ 3555  
set w/ 100 sk Cem. Perf. at 3425 no plugs below.  
Filled hole back with crushed rock to 3400'  
and dumped 5 sk Cem. Shot off and pulled 5 1/2"  
casing. Pumped in 20 sk of fresh fill mud,  
plug, and 125 sk of Cem. Filling hole and  
surface casing from approx 200' to base of  
cellar with Cem. Sun. Cem. Co.

RECEIVED  
STATE CORPORATION COMMISSION

Warren H. Harner  
District Conservation Agent

Date May 7, 1954

PLUGGING  
FILE SEC 32 T 20 R 13w  
BOOK PAGE 4 LINE 32

MAY 10 1954  
CONSERVATION DIVISION  
Wichita, Kansas