

ML
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 11 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Alpine Oil & Royalty Co., Inc.

Complete Address: 800 Bitting Bldg., Wichita, Kansas

Lease Name Clarence Denbo Well No. # 1

Location SE SE SW Sec. 26 Twp. 20 Rge. 13 (E) (W)

County Barton Total Depth 3570

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glenn & Smith Pipe Pulling Co.

Address: 204 E. 6th., Ellinwood, Kansas License No. 396

Operation Completed: Hour 11:30AM Day 6 Month 3 Year 1963

The Above well was plugged as follows:

8 5/8" 205' Gwc.

Set bottom plug @ 3280' & dumped 4 sax cement with dump bailer.

Pulled pipe. Mudded hole to 205'; set rock bridge; dumped 6 sax cement
with dump bailer. Allowed to set over night; bailed hole dry; displaced
20 sax cement. Mud to 40'; set rock bridge; displaced 10 sax cement,
cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don Truman
Well Plugging Supervisor

DATE 3/12/63

INV. NO. 6694-W