



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 4 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Woodman & Iannitti Oil Company

Complete Address 1008 Union Nat'l. Bldg., Wichita, Kansas

Lease Name Denbo Well No. # 1

Location NE SW SE Sec. 26 Twp. 20 Rge. 13 (E) (W) W

County Barton Total Depth 3537

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Same with Co. tools

Address Same License No.

Operation Completed: Hour 11:30 A.M. Day 1 Month 9 Year 1974

The above well was plugged as follows:

8 5/8" csg. 209' Cwc.
Circulated hole with heavy mud to 500', set plug, & displaced 40 sax cement thru
drill pipe. Mud to 200' & displaced 25 sax cement thru drill pipe. Mud to 40',
1/2 sax hulls, plug, & displaced 10 sax cement with Sun Cementing Company's pump
truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Don Luman
Well Plugging Supervisor

INVOICED

DATE 9/4/74

INV. NO. 9836-W