

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-29300-00-00
Spot: NWSWSEW Sec/Twnshp/Rge: 34-26S-16E
3110 feet from S Section Line, 3734 feet from E Section Line
Lease Name: MEARS LEASE M Well #: M-21
County: WOODSON Total Vertical Depth: 1060 feet

Operator License No.: 33718
Op Name: MEARS, JOHN C.
Address: 4100 240TH RD
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	7	40		
PROD	2.875	1044		125 SX
SURF	7	40		8 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/28/2017 12:00 PM
Plug Co. License No.: 33977 Plug Co. Name: E K ENERGY LLC
Proposal Revd. from: DAVID KIMZEY Company: E K ENERGY LLC Phone: (620) 496-6257

Proposed Plugging Method: fill casing with cement top to bottom

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 11/28/2017 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

The wellhead was connected to and circulation established by pumping 10 bbls of water. The well was then pumped full of cement that contained cottonseed hulls by squeezing. The well was shut in with 750 psi. A total of 34 sacks of portland cement were used to plug well.

RECEIVED
KCC DIST #3
FEB 07 2018
CHANUTE, KS

AD

INVOICED

MAR - 8 2018

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)