

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-00432-00-01
Spot: SESESWSE Sec/Twnshp/Rge: 31-33S-37W
118 feet from S Section Line, 1321 feet from E Section Line
Lease Name: HALL Well #: 1-31
County: STEVENS Total Vertical Depth: 2875 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY, LLC
Address: 13727 NOEL ROAD, SUITE 1200
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2570		WITH 2 SX CMT
PROD	4.5	2856	0	WITH 550 SX CMT
SURF	8.625	680		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/09/2018 10:00 AM
Plug Co. License No.: 35195 Plug Co. Name: SURE ENERGY SERVICE, LLC
Proposal Rcvd. from: GRANT YEATMAN Company: SURE ENERGY SERVICE, LLC Phone: (806) 228-6049

Proposed Plugging Method: SET CIBP @ 2570' WITH 2 SX CMT. PLUG AT 1700' WITH 30 SX CMT. RUN CBL TO DETERMINE TOC.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 02/09/2018 2:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

2/7/18: SET CIBP @ 2570' WITH 2 SX CMT. 1ST PLUG AT 1700' WITH 30 SX CMT.
2/8/18: TAGGED CMT AT 1260'. RAN CBL & FOUND TOC AT 100'. 2/9/18: 2ND PLUG
AT 720' WITH 70 SX CMT TO SURFACE. PUMPED 5 SX CMT DOWN BACKSIDE &
PRESSURED TO 400 PSI.

Perfs:

Top	Bot	Thru	Comments
2611	2820		

INVOICED
MAR - 8 2018

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED COMMON CEMENT BY SURE ENERGY.

Plugged through: TBG

District: 01

Signed

K. M. Sullivan

(TECHNICIAN)

SA

RECEIVED
FEB 13 2018
KCC DOUGIE CITY

MR