

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-20427-00-00

Spot: S2S2S2NW

Sec/Twnshp/Rge: 3-34S-40W

2789 feet from S Section Line, 3905 feet from E Section Line

Lease Name: STOUT D E

Well #: 2

County: MORTON

Total Vertical Depth: 3000 feet

Operator License No.: 32446

Op Name: MERIT ENERGY COMPANY, LLC

Address: 13727 NOEL ROAD, SUITE 1200
DALLAS, TX 75240

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comments</u>
PROD	5.5	3000	0	WITH 750 SX CMT
SURF	8.625	631		WITH 400 SX CMT

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 02/08/2018 1:00 PM

Plug Co. License No.: 99996

Plug Co. Name: BJ SERVICES, LLC

Proposal Revd. from: JOHN COMBS

Company: BJ SERVICES, LLC

Phone: (620) 624-5937

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: SCOTT ALBERG

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 02/09/2018 1:00 PM

KCC Agent: HEITH WALSH

Actual Plugging Report:

Perfs:

2/8/18: FOUND TBG FREE POINT AT 1900' & CUT TBG AT 1900'. TOO H WITH TBG. RTIH TO 1890'. 1ST PLUG AT 1890' WITH 100 SX CMT & 150# HULLS. RAN CBL & TOC @ 250'. SDON. 2/9/18: TAG TOC @ 1040'. PRESSURE TESTED 5 1/2" CASING TO 300# & IT HELD. RTIH TO 670'. 2ND PLUG AT 670' WITH 30 SX CMT. TOO H WITH TBG. PERFORATE AT 230'. 3RD PLUG CIRCULATE 70 SX CMT FROM 230' TO SURFACE INSIDE & OUTSIDE.

<u>Top</u>	<u>Bot</u>	<u>Thru</u>	<u>Comments</u>
2780	2926		

INVOICED

MAR - 8 2018

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY BJ SERVICES.

Plugged through: TBG

District: 01

Signed

[Signature]

(TECHNICIAN)

RECEIVED

FEB 16 2018

KCC DODGE CITY