

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-24738-00-00  
Spot: NWSENWSW Sec/Twnshp/Rge: 34-19S-23W  
1865 feet from S Section Line, 4348 feet from E Section Line  
Lease Name: ROBERT Well #: 1-34  
County: NESS Total Vertical Depth: 4480 feet

Operator License No.: 5144  
Op Name: MULL DRILLING COMPANY, INC.  
Address: 1700 N WATERFRONT PKWY BLDG 120  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4320		WITH 2 SX CMT
PC		1536		CEMENTED TO SURFACE
PROD	5.5	4479	0	WITH 145 SX CMT
SURF	8.625	205		WITH 160 SX CMT

Well Type: OIL UTC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/23/2015 12:15 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: KYLE RANDA Company: MULL DRILLING Phone: (785) 798-0591

Proposed Plugging Method: CIBP 50' ABOVE PERFS & 2 SX CMT. SWAB CASING DOWN TO 1600' & FILL WITH CMT. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/23/2018 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4320' WITH 2 SX CMT. SWAB CASING DOWN TO 1600'. FILL THE CASING WITH CMT TO SURFACE USING 150 SX CMT. PUMP 45 SX CMT DOWN THE ANNULUS. PRESSURED TO 200#.

Perfs:

Top	Bot	Thru	Comments
4368	4378		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

*[Handwritten Signature]*  
5A

(TECHNICIAN)

RECEIVED  
JAN 29 2018  
KCC DODGE CITY *[Handwritten Initials]*