

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-25510-00-00  
Spot: NENWSWSW Sec/Twnshp/Rge: 17-14S-16W  
1232 feet from S Section Line, 4891 feet from E Section Line  
Lease Name: SCHIPPERS Well #: 1-17  
County: ELLIS Total Vertical Depth: 3500 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3490		150 SX
SURF	8.625	303		180 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/12/2018 9:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: CRAIG HUTCHINSON Company: MURFIN DRILLING CO., INC. Phone: (800) 433-9047

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/700 # hulls.  
Casing leaks at 2643'.  
Port Collar at 1065' w/130 sx cement.  
Perforations: 3280' - 3325' and 3394' - 3399'.  
PBSD: 3437'

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/12/2018 12:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Murfin ran in hole with tubing to 3260'. Hurricane Service rigged to tubing and pumped 150 sx cement w/300 # hulls. Pulled tubing to 1760' and pumped 100 sx cement w/200 # hulls mixed in. Pulled tubing to 760' and pumped 75 sx cement w/100 # hulls to circulate cement to surface. Pulled tubing. Topped off 5 1/2" casing with 15 sx H.S.F Rigged to 8 5/8" surface casing and pumped 15 sx cement. Cement came out of ground around head.

GPS: 38.83097 -099.13092

Perfs:

Top	Bot	Thru	Comments
3394	3399		
3322	3325		
3280	3284		

Remarks: HURRICANE CEMENTING CO TICKET # 100877

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

LM

Received  
KANSAS CORPORATION COMMISSION

FEB 23 2018

CONSERVATION DIVISION  
WICHITA, KS

FEB 16 2018

Form CP-2/3

INVOICED  
MAR -0 2018