

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-29002-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 12-34S-13E
3098 feet from S Section Line, 2283 feet from E Section Line
Lease Name: BLASI Well #: G-1
County: MONTGOMERY Total Vertical Depth: 1577 feet

Operator License No.: 8704
Op Name: PITMAN, JOHN ESTATE (DECEASED)
Address: 222 E. SHERIDAN #7
OKLAHOMA CITY, OK 73104

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1577		35 SX
SURF	7	20		5 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/25/2018 12:00 AM
Plug Co. License No.: 31696 Plug Co. Name: CUNNINGHAM CRUDE. A GENERAL PARTNERSHIP
Proposal Rcvd. from: RON CUNNINGHAM Company: _____ Phone: (620) 289-4700

Proposed Plugging Method: RUN TBG TO BTM, GEL HOLE, SPOT 5 SX ON BTM, PULL UP TO 500', SPOT 5 SX, PULL UP TO 225', CMT TO SURF. PULL TBG OUT OF HOLE, TOP OF CMT, CUT WELLHEAD BLW PLOW DEPTH.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 01/25/2018 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" tubing to 1500' and gelled hole and spotted 5 sack plug. Pulled up to 500' and spotted 5 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 2" and topped well off. A total of 28 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

RECEIVED
KCC DIST # 3
FEB 20 2018
CHANUTE, KS

DS


INVOICED

Remarks: WELL WAS PLUGGED DUE TO LETTER SENT TO OPERATOR BY LEGAL STAFF IN WICHITA - 6 2018

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)