

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-22732-00-00
Spot: N2SESESE Sec/Twnshp/Rge: 29-23S-11E
355 feet from S Section Line, 330 feet from E Section Line
Lease Name: EDWARDS Well #: 4
County: GREENWOOD Total Vertical Depth: 2010 feet

Operator License No.: 7564
Op Name: R & W ENERGIES, A GENERAL PARTN
Address: 403 N. MYRTLE
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2010		98 SX
SURF	8.625	420		280 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/15/2018 9:00 AM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Rcvd. from: BRYAN MARSHALL Company: _____ Phone: (620) 583-4785

Proposed Plugging Method: Per KCC

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/15/2018 12:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 1974', pumped 25 sxs cement, pulled tubing to 900', pumped 10 sxs cement, pulled tubing to 250', pumped pumped 75 sxs cement to surface, casing shot @ 900' & 250', gel spacers between cement plugs.

Perfs:

RECEIVED
KCC DIST #3
FEB 19 2018
CHANUTE, KS

MH

INVOICED
MAR - 6 2018

Remarks:
Plugged through: TBG

District: 03

Signed Mike Heffern
(TECHNICIAN)

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



15-093-22732

Cement or Acid Field Report
 Ticket No. 3755
 Foreman Steve Mead
 Camp Eureka, KS

Date	Cust. ID#	Lease & Well Number	Section	Township	Range	County	State	
2-15-18	1163	Lucky Edward # 4				Greenwood	KS	
Customer Marshall Oil LLC			Safety Meeting		Unit #	Driver	Unit #	Driver
Mailing Address P.O. Box 389					102	RICK		
City Eureka					110	Dave		
State KS		Zip Code 67045						

Job Type PIA old well Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8 1974'
 Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 3 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting: Rig up to 2 3/8 Tubing Break Circulation w/ Fresh Water.
Pump 300" Gel. Plug Well AS Follow.

25 sks AT 1974'

10 sks AT 900'

75 sks - 250' TO SURFACE

Total 110 sks 60/40 permix Cement 4% Gel

Job Complete Thank You

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-105	1	Pump Charge	750.00	750.00
C-107	15	Mileage	3.95	59.25
C-203	110 sks	60/40 permix Cement	12.75	1402.50
C-206	375#	Gel 4%	1.20	75.00
C-206	300#	Gel Spacer	1.20	60.00
C-214	20#	Hulls	.45	9.00
C-108A	4.73 Ton	Ten Mileage Bulk Truck	M/K	200.00
<div style="border: 1px solid black; border-radius: 50%; padding: 10px; display: inline-block;"> 5% (131.38) \$ 2610.05 </div>				
			Sub Total	2555.75
			2.50% Sales Tax	191.68
Authorization <u>Bryan Marshall</u> Title <u>Co. Rep</u>			Total	<u>2747.43</u>

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.