

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22921-00-00
Spot: SESENW Sec/Twnshp/Rge: 33-31S-13W
2973 feet from S Section Line, 2986 feet from E Section Line
Lease Name: DUGAN TRUST E Well #: 1
County: BARBER Total Vertical Depth: 4550 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2600		WITH 2 SX CMT
PROD	4.5	2820	2012	WITH 150 SX CMT
SURF	10.75	291		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/24/2018 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 2600' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 320' WITH 75 SX CMT. PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: PARTIAL
Date/Time Plugging Completed: 01/24/2018 10:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 2810'. SET CIBP @ 2600' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 607' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 325' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 75 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2658	2663		

INVOICED
MAR 7 2018

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
JAN 29 2018
KCC DODGE CITY