

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23134-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 25-18S-24W
990 feet from S Section Line, 4950 feet from E Section Line
Lease Name: MAIER Well #: 3
County: NESS Total Vertical Depth: 4274 feet

Operator License No.: 8247
Op Name: RF HEMBREE OIL, LLC
Address: PO BOX 542
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	1535		WITH 100 SX CMT
PROD	5.5	4260	0	WITH 110 SX CMT
SURF	8.625	300		WITH 180 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/25/2018 8:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: FRED J. HEMBREE Company: FRED HEMBREE Phone: (620) 802-7960

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 70 SX CMT & 500# HULLS. PULL TBG TO 1550' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & FILL WITH CMT.

Plugging Proposal Received By: KEN SCOFIELD Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/25/2018 12:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4261' & PUMED 70 SX CMT & 200# HULLS. PULLED TBG TO 1550' & PUMPED 190 SX CMT & 200# HULLS. LOST CIRCULATION. PULLED TBG & WAITED 2 HOURS. RAN TBG IN TO 1550' & PUMPED 135 SX CMT & 400# HULLS. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4260	4274	OH	

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

MAR - 7 2018

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
JAN 30 2018
KCC DODGE CITY