

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-133-26793-00-00
Spot: NWSESENE Sec/Twnshp/Rge: 1-29S-19E
2009 feet from N Section Line, 379 feet from E Section Line
Lease Name: RIVER FARMS INC Well #: 1-2
County: NEOSHO Total Vertical Depth: 880 feet

Operator License No.: 35341
Op Name: RIVER ROCK OPERATING, LLC
Address: 211 N. ROBINSON SUITE 200
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	873		127 SX
SURF	8.625	42		30 SX
T1	2.375	812		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 01/22/2018 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (405) 606-7481

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 01/22/2018 10:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to TD and the well pumped full of cement from btm to top thru the cement string. According to operator a total of 86 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
775	778		
722	724		
716	718		
565	567		
508	510		
479	482		
453	455		
359	363		
348	352		

RECEIVED
KCC DIST # 3
FEB 21 2018
CHANUTE, KS

ADVISED

MAR - 7 2018

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning

(TECHNICIAN)