

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-27016-00-00  
Spot: SESE Sec/Twnshp/Rge: 31-27S-16E  
660 feet from S Section Line, 660 feet from E Section Line  
Lease Name: HARVEY, LEONARD H. Well #: 31-1  
County: WILSON Total Vertical Depth: 1249 feet

Operator License No.: 35341  
Op Name: RIVER ROCK OPERATING, LLC  
Address: 211 N. ROBINSON SUITE 200  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1231		164 SX
SURF	8.625	21		5 SX
T1	2.375	936		

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/25/2018 11:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Revd. from: BRANDON DONOVAN Company: RIVER ROCK OPERATING Phone: (405) 606-7481

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE  
Date/Time Plugging Completed: 01/25/2018 11:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to TD. The well was pumped full of cement from btm to top thru the cement string. A total of 123 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
951	953		
938	940		
885	888		
868	870		
794	798		
783	953		

RECEIVED  
KCC DIST #3  
FEB 21 2018  
CHANUTE, KS

AD

Remarks:

Plugged through: CSG

INVOICED

MAR - 7 2018

District: 03

Signed

Alan Dunning

(TECHNICIAN)