

STATE OF KANSAS
STATE CORPORATION COMMISSION

**Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas**

NORTH

***Locate well correctly on above
Section Plat**

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

McPherson.....County. Sec. 4.....Twp. 20.....Rge. 3.....(E).....(W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines.....SW SW NE

Lease Owner.....Globe Oil & Refining Company - Kansas.....

Lease Name.....**Strouse**..... Well No.....**1**.....

Office Address.....301 S. Market, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date, well completed.....January 21.....19 43

Application for plugging filed..... January 22 19 43

Application for plugging approved January 22 19 43

Plugging Commenced January 22 19 43

Plugging Completed.....January 22.....19. 43

Reason for abandonment of well or producing formation.....Dry.....

If a producing well is abandoned, date of last production.....19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well.....Ruel Durkee.....

Producing formation..... Depth to top..... Bottom..... Total Depth of Well.....3807' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Filled hole with mud from total depth to base of surface pipe, set wooden plug in base of 8" at 190 feet and cemented with 10 sacks of cement, 5 sacks of cement in base of cellar and steel plate welded on top of casing.

pd
r/b/4 3

FILE 4-20-3W
BOOK PAGE 61 LINE 22

2-15-1943

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....
Address.....
H. E. Miller
Lario Oil & Gas Company
Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick
Leo Ross (employee of owner) or (owner or operator) of the above described well

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo Koss

301 S. Market Street, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of February, 1943

My commission expires Sept 23, 1946 Notary Public.

STROUSE, NO. 1 WELL

C SW SW NE Sec. 4-20S-3W,
McPherson County, Kansas.Drilled for: Globe Oil & Refining Company
Drilled by: Boardmore Drilling Company

Casing Record:

8-5/8" 201'

Drilling Commenced: December 12, 1942.
Drilling Completed: January 21, 1943.

D.Y.A.

FORMATION


DEPTH

surface	201
shale & shells	470
lime	555
lime (broken)	1100
lime (hard)	1185
lime	1410
shale & lime	1880
lime	1960
shale & lime	2190
shale & shells	2280
shale	2475
lime	2510
shale & lime	2700
lime	2785
shale & lime	3070
shale	3135
chat	3137
lime	3196
chat	3214
chat (broken)	3234
lime (broken)	3240
shale & lime	3275
lime (hard)	3289
chat	3298
chat (broken) & lime	3310
chat & lime	3336
chat (broken) & lime	3354
lime (hard)	3369
lime	3480
shale	3634
lime	3671
shale	3678
lime (hard)	3727
lime	3807 T.D.

STATE OF KANSAS

SS.

COUNTY OF SEDGWICK



I, the undersigned, being duly sworn on oath, state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.

Subscribed and sworn to before me this 30th day of January, 1943.

Notary Public

My Commission Expires December 6, 1943.

FEB 23 1943