

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15.009.05278.0000

BARTON County, Sec. 33 Twp. 20S Rge. 13W (W)

NORTH

	Sec. 33		

Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines NE NE SW
 Lease Owner PETROLEUM, INC.
 Lease Name Hiss "C" Well No. 2
 Office Address ROUTE 2, GREAT BEND, KANSAS
 Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
 Date well completed NOVEMBER 11, 1962
 Application for plugging filed NOVEMBER 11, 1962
 Application for plugging approved NOVEMBER 11, 1962
 Plugging commenced NOVEMBER 11, 1962
 Plugging completed NOVEMBER 11, 1962
 Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES
 If a producing well is abandoned, date of last production NONE 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well DONALD TRUAN
 Producing formation --- Depth to top --- Bottom --- Total Depth of Well 3604 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	325'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MUDDERED UP WITH HEAVY MUD TO 300' FOLLOWED BY WOODEN PLUG AND 1/4 SACK HULLS. PLACED 25 SACKS CEMENT THROUGH DRILL PIPE ON TO HULLS. MUDDERED UP WITH HEAVY MUD TO 35' FOLLOWED BY WOODEN PLUG, 1/2 SACKS HULLS AND 10 SACKS CEMENT TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

DEC 17 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY
 Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
 (Signature) Don Searle DON SEARLE, DIST. PROD. SUPT.
ROUTE 2, GREAT BEND, KANSAS
 (Address)

SUBSCRIBED AND SWORN TO before me this 14TH day of DECEMBER, 19 62

My commission expires APRIL 12, 1963

Arthur J. Miles
Notary Public.



WELL LOG

15.009.05278.0000

COMPANY PETROLEUM, INCORPORATED

SEC. 33 T-20S R. 13W

FARM HISS "C" NO. 2


LOC. NE, NE, SW

TOTAL DEPTH 3604'

COUNTY BARTON CO., KANSAS

COMM. November 3, 1962 COMP. November 11, 1962

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8-5/8" @ 325' w/275 sax.

ELEVATION 1896' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

295	Surface soil & sand
325	Shale
770	Red bed & shale
795	Anhydrite
1555	Shale & shells
1660	Shale & lime
2260	Lime
2853	Shale & lime
3008	Lime & shale
3138	Lime
3159	Lime & shale
3164	Shale
3198	Lime & shale
3272	Sandy shale
3525	Lime
3563	Lime & shale
3604	Lime
3604	T. D.

RECEIVED
STATE CORPORATION COMMISSION

DEC 17 1962

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS
County of BARTON } ss

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #2 HISS "C" well.

Verne A. Morris

Subscribed and sworn to before me this 5th day of December 19 62

My Commission Expires: April 14, 1963

Arthur J. Mule
NOTARY PUBLIC