


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 33 Twp. 20S Rge. 13 (E) (W) X

Location as "NE/CNW/SW" or footage from lines NE NE NW

Lease Owner Circle Oil Company, Inc.

Lease Name Hiss Well No. 1

Office Address 500 Bitting Building Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 7-7-67 19

Application for plugging approved 7-8-67 19

Plugging commenced 8-16-67 19

Plugging completed 8-30-67 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving

Producing formation Depth to top Bottom Total Depth of Well 3637 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 217 | None |
| | | | | 5 1/2 | None | 2725 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Cleaned out cellar.

Sanded to 3550'. Dumped 5 sacks of cement. Working pipe. Shot pipe at 3000'.

Working pipe. Shot pipe at 2900' - 2800' and 2715'. Circulating. Spotted 50 bbl of oil.

Working pipe.

Pulling pipe.

Squeezed well with 20 sacks of mud and 85 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 5 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. J. O. Forbes

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 31 day of August, 1967

My commission expires May 27, 1969

Notary Public.

DRILLERS LOGHISS NO. 1

| | | | |
|-----------------------------------|-------------|----------------------|---|
| CASING RECORD: | COMPANY: | Circle Oil Co., Inc. | DESCRIPTION: |
| 8-5/8" @ 217' w/250 sax cement | CONTRACTOR: | Sage Drilling Co. | NE NE NW Sec. 33-20S-13W Barton Co., Kansas |
| | COMMENCED: | June 25, 1965 | |
| TOTAL DEPTH: 3635' | COMPLETED: | July 2, 1965 | ELEVATION: 1895 KB |

| <u>FORMATION</u> | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u> |
|----------------------|-------------|-----------|----------------|
| Sand | 0 | 95 | |
| Hard Sand | 95 | 123 | |
| Sand | 123 | 175 | |
| Shale | 175 | 217 | |
| Shale & Sand | 217 | 525 | |
| Shale & Shells | 525 | 759 | |
| Anhydrite | 759 | 780 | |
| Shale & Shells | 780 | 1550 | |
| Sandy Lime & Shale | 1550 | 1610 | |
| Lime & Shale | 1610 | 2938 | |
| Cherty Lime & Shale | 2938 | 3095 | |
| Lime & Shale | 3095 | 3188 | |
| Shale | 3188 | 3278 | |
| Lime & Shale | 3278 | 3300 | |
| Lime | 3300 | 3500 | |
| Lime & Shale Streaks | 3500 | 3565 | |
| Cherty Lime | 3565 | 3585 | |
| Lime & Shale | 3585 | 3635 | |

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1967
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING COMPANY, INC.

Lawrence F. Gray
Lawrence F. Gray

Subscribed and sworn to before me this 9th day of July, 1965.

Louise K. Whitted
Louise K. Whitted, Notary Public

My Commission expires:
November 26, 1966.