

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Barton County, Sec. 32 Twp. 20 Rge. 13 (E) (W)

Location as "NE/CNW/SW%" or footage from lines SE NE SW

Lease Owner Ben F. Brack Oil Company, Inc.

Lease Name Wright Well No. 2

Office Address 309 Brown Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 3-11-49 19

Application for plugging filed 5-13-53 19

Application for plugging approved 5-15-53 19

Plugging commenced 5-24-53 19

Plugging completed 6-1-53 19

Reason for abandonment of well or producing formation uneconomical

If a producing well is abandoned, date of last production May 10, 19 53

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Arbuckle Depth to top 3553' Bottom 3563' Total Depth of Well 3563' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Soil, Sand & Gravel	Dry	0	142'	8 5/8"	142'	None
Kansas City Lime		3302	3535			
Detrital Zone		3535	3553			
Arbuckle		3553	3563	5 1/2"	3553	1920'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back from 3556-3500' with sand. Plugged back from 3500-3465' with 5 sax cement. Shot pipe @ 1920'. Pumped in 30 sax Magcogel and 60 sax cement. Squeezed surface pipe with 40 sax cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pulling, Cinc.

Address 629 West Broadway, Stafford, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

Leland E. Brack (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *Leland E. Brack*

309 Brown Bldg., Wichita, Kansas

(Address)

Subscribed and Sworn to before me this 9th day of June, 1953

My commission expires June 11, 1955



*Certude Crist*  
Notary Public.

**PLUGGING**  
FILE SEC 32 T 20 R 434  
BOOK PAGE 101 LINE 15

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 11 1953  
CONSERVATION DIVISION  
Wichita, Kansas

BEN F. BRACK OIL COMPANY, INC.  
310 Brown Building  
Wichita, Kansas

Wright No. 2 SE NE SW, Section 32, T. 20 S., R. 13 W., Barton County, Kansas

WELL LOG

TOTAL DEPTH	3556'
Comm: 2-23-49	Comp: 3-11-49
Cellar	5'
Sand and Blue Shale	130
Sand and Blue Shale	155
Sand and Shale	330
Shale and Shells	475
Red Bed	785
Anhydrite	825
Red Bed and Shale	870
Red Bed and Shale	1130
Shale and Shells	1340
Shale and Lime	1595
Lime	1675
Lime	1790
Lime	1890
Lime	1985
Sandy Lime and Shale	2080
Lime	2150
Lime	2160
Lime and Shale	2250
Lime and Shale	2315
Lime and Shale	2395
Lime and Shale	2470
Broken Lime and Shale	2550
Shale	2660
Shale and Lime	2720
Lime and Shale	2755
Shale and Lime	2830
Lime and Shale	2900
Lime and Shale	2965
Lime and Shale	3005
Lime	3050
Lime	3085
Lime	3130
Lime	3167
Lime	3195
Lime	3265
Lime	3308
Lime	3340 (Top K. C. 3303')
Lime	3360
Lime	3400
Lime	3433
Lime	3460
Lime	3469
Lime	3490
Lime	3535
Lime and Arbuckle	3556 (Top Arbuckle 3553')
TOTAL DEPTH	3556

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 15 1953  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 32 T 20 R 13 W  
BOOK PAGE 101 LINE 137

Dated: 3-17-49

Witness: Paulus H. ...

To the best of my knowledge the above is a true and correct record of the formations and depths at which found.

BEN F. BRACK OIL COMPANY, INC.

By Bill A. Brack  
President