

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

BARTON County. Sec. 32 Twp 20S Rge. 13 (X) (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NE NE SW
Lease Owner BEN F. BRACK OIL COMPANY, INC.
Lease Name WRIGHT Well No. 1 "A"
Office Address 309-10 BROWN BUILDING, WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed 12-1-49 19__
Application for plugging filed 1-19-50 19__
Application for plugging approved 1-19-50 19__
Plugging commenced 1-19-50 19__
Plugging completed 1-23-50 19__
Reason for abandonment of well or producing formation no oil



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. STROUGH
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3481 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand Surface, soil & Clay		0	328	8-5/8	237	
Conglomerate	Good Staining slight odor		3481	5 1/2"	3612'3"	2321'6"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 328 feet to 35 feet for each plug set.

Plugged back from 3371 to 3290' with Chat. Dumped 5 sacks cement. Mudded hole to 328' Set 10' rock bridge, dumped 15 sacks cement. Mudded to 35'. 10 sacks cement.

2-15-1950
RECEIVED
Conservation Div.
FEB 15 1950
STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to BEN F. BRACK OIL COMPANY, INC.
Address 309-10 BROWN BUILDING, WICHITA, KANSAS.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
HENRY B. BRACK (employed by owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Henry B. Brack

BEN F. BRACK OIL CO. INC. 309-10 Brown BUILDING, WICHITA 2 KANSAS.

SUBSCRIBED AND SWORN to before me this 14th day of February, 1950

Lucille A. Buerling
Notary Public.

My commission expires October 5, 1953



BEN F. BRACK OIL COMPANY, INC.

15.009.05872.0000

WRIGHT NO. 1-A NE NE SW ~~(X)(X)~~ 32-20S-13W Barton County, Kansas.

COMMENCED: 11-18-49

COMPLETED: 12-1-49

Total depth: 3481'

WELL LOG

Cellar	5'
Surface Soil and Sand	75
Sand	120
Shale	130
Shale Iron	150
	163
Shale and Clay	255
Shale	315
Sand	328
Red Bed	800
Anhydrite top	800
Anhydrite	812
Shale and Shells	940
Shale	1300
Salt	1440
Shale and Lime	1630
Shale	1750
Broken Lime	1800
Shale-Lime	1950
Lime	2030
Shale and Lime	2105
Lime and Shale	2195
Lime and Shale	2270
Shale	2385
Shale	2485
Shale and Lime St.	2560
Broken Lime	2690
Shale and Lime	2810
Lime	2885
Broken Lime	2970
Lime	3015
Lime and Shale	3070
Lime 3135	3135
Lime	3175
Lime	3220
Lime	3290
Lime	3340
Lime	3370
Lime	3415
Lime 3465	3465
Lime	3481
TOTAL DEPTH	3481

5 1/2" Casing cemented @ 3480'

To the best of my knowledge, the above is a true and correct copy of all formations and where found.

BEN F. BRACK OIL COMPANY, INC.

Witness:
L. A. ...

B. F. Brack
BY
Vice-President

DATED: December 10, 1949

PLUGGING
FILE SEC 32 T 2 R 13
BOOK PAGE 135 LINE 17

RECEIVED
Conservation Div.
FEB 15 1950
STATE CORPORATION
COMMISSION
KANSAS