

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 32 Twp. 20S Rge. 13 (X) (W)

Location as "NE/CNW/SW" or footage from lines. NE NE SW

Lease Owner Ben F. Brack Oil Company, Inc.

Lease Name Wright Well No. 1

Office Address 309 Brown Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 12-5-48 19

Application for plugging filed 12-30-53 19

Application for plugging approved 12-31-53 19

Plugging commenced 5-7-54 19

Plugging completed 5-10-54 19

Reason for abandonment of well or producing formation oil depleted

If a producing well is abandoned, date of last production 12-11-53 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Horner

Producing formation Arbuckle Depth to top 3545' Bottom 3561' Total Depth of Well 3561' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand, Gravel & Iron		0'	141'	8 5/8"	141'	None
Anhydrite		775'	815'			
Kansas City		3297'				
Arbuckle		3545'	3561'	5 1/2"	3546'	312'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3400' feet to 3365' feet for each plug set.

Plugged back with crushed rock from 3561' to 3400'. Dumped 5 sax cement with dump bailer at 3400', top of cement - 3365'. Pumped in 20 sax mud and 125 sax cement with Halliburton. Levelled location.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. & M. Casing Pulling Company


Address P. O. Box 711, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Ben F. Brack (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ben F. Brack

309 Brown Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 17th day of May, 1954



Gertrude Crist Notary Public.

My commission expires June 11, 1955.

PLUGGING
FILE SEC 32 T 20 R 13W
BOOK PAGE 4 LINE 33

CONSERVATION DIVISION

5-19-1954

BEN F. BRACK OIL COMPANY, INC.
310 Brown Building
Wichita, Kansas

Wright #1 NE NE SW Section 32, Township 20 South, Range 13 West,
Barton County, Kansas

WELL LOG

TOTAL DEPTH	3561
Comm: 11-12-48	Comp: 11-26-48
Cellar	5'
Sand, Gravel and Iron	140
Blue Clay	260
Sand	320
Red Bed	630
Red Bed, Shale & Anhydrite	940
Anhydrite	775-815
Red Shale and Salt	1245
Salt and Shale	1550
Shale	1590
Lime and Shale	1690
Lime and Shale	1790
Lime	1890
Lime	1990
Lime	2025
Lime	2110
Lime and Shale	2220
Lime and Shale	2310
Lime and Shale	2410
Shale and Lime	2515
Shale and Shells	2660
Shale and Lime	2760
Shale and Lime	2860
Lime, broken	2950
Lime and Shale	3010
Lime	3085
Lime and Shale	3140
Lime	3176
Lime and Shale	3260
Shale and Lime	3330
Shale and Lime	3385
Lime	3430
Lime	3470
Lime	3535
Lime	3545
Arbuckle	3561
Total Depth	3561

Dated: November 29, 1948

Witness: Paulene Henderson

To the best of my knowledge the
above is a true and correct record of the
formations and depths at which found.

BEN F. BRACK OIL COMPANY, INC.

By: Paul Henderson

LOGGING
FILE SEC 32 T 20 R 13
BOOK PAGE 4 LINE 33