

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

| | | | |
|--|---|--|--|
| | | | |
| | | | |
| | X | | |
| | | | |

Locate well correctly on above Section Plat

Barton County, Sec. 32 Twp. 20S Rge. 13 (X) (W)
Location as "NE/CNW/SW" or footage from lines NW NE SW
Lease Owner Ben F. Brack Oil Company, Inc.
Lease Name Wright Well No. 3
Office Address 309 Brown Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed October 19 49
Application for plugging filed 12-30-53 19
Application for plugging approved 12-31-53 19
Plugging commenced 5-3-54 19
Plugging completed 5-7-54 19
Reason for abandonment of well or producing formation oil depleted

If a producing well is abandoned, date of last production 12-11-53 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Horner
Producing formation Arbuckle Depth to top 3553' Bottom 3570' Total Depth of Well 3570' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|---------------------|---------|------|------|--------|--------|------------|
| Clay, Sand & Shells | | 0 | 149 | 10" | 149' | None |
| Brown Lime | | 3286 | | | | |
| Lansing | | 3305 | | | | |
| Arbuckle | | 3553 | 3570 | 5 1/2" | 3554' | 2592' |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3400' feet to 3365' feet for each plug set.

Filled with crushed rock from 3564' to 3400'. Dumped 5 sax cement at 3400' with dump bailer - top of cement 3365'. Pumped in 20 sax mud and 125 sax cement by Halliburton. Levelled location.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J & M Casing Pulling Company
Address Box 711, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Ben F. Brack (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ben F. Brack
309 Brown Bldg., Wichita 2, Kansas (Address)

Subscribed and sworn to before me this 17th day of May, 19 54
Gertrude Crist
Notary Public.



PLUGGING
FILE SEC 32 T 20S R 13W
BOOK PAGE 4 LINE 32

5-19-1954

WRIGHT #3 - NW NE SW of Section 32, Township 20 South, Range 13 West
Barton County, Kansas.

Commenced - 9-3-49

Completed 9-18-49

Total Depth - 3569'

WELL LOG

| | |
|---------------------------|------|
| Cellar | 5 |
| Clay Sand and Shells | 149 |
| Shale | 187 |
| Shale- | 191 |
| Shale Shells | 300 |
| Shells - Red Bed | 375 |
| Shale and Shells | 700 |
| Shale and Shells | 790 |
| Sandhyrite | 820 |
| Red Bed, Shale and Shells | 1040 |
| Shale and Shells | 1420 |
| Salt and Shale | 1610 |
| Lime and Shale | 1692 |
| Lime and Shale | 1800 |
| Lime | 1955 |
| Lime and Shale | 2050 |
| Lime and Shale | 2150 |
| Lime | 2200 |
| Lime and Shale | 2285 |
| Lime and Shale | 2360 |
| Lime and Shale | 2470 |
| Lime and Shale | 2570 |
| Lime and Shale | 2610 |
| Lime and Shale | 2700 |
| Shale | 2770 |
| Shale and Shells | 2805 |
| Shale and Shells | 2895 |
| Shale, Shells and Lime | 2980 |
| Lime | 3028 |
| Lime | 3052 |
| Lime and Shale | 3100 |
| Lime and Shale | 3133 |
| Lime & Chert | 3160 |
| Lime and Shale | 3220 |
| Lime and Shale | 3288 |
| Lime | 3332 |
| Lime | 3357 |
| Lime | 3400 |
| Lime | 3430 |
| Lime | 3432 |
| Lime | 3467 |
| Lime | 3510 |
| Lime | 3549 |
| Lime | 3555 |
| Arbuckle | 3569 |
| TOTAL DEPTH | 3569 |

Pip set at 3554'

WITNESS:

Lucille A. Brack

To the best of my knowledge, the above is a true and correct copy of all formations and where found.

BEN F. BRACK OIL COMPANY, INC.

By: *Lucille A. Brack*
Vice President

Dated: October 4, 1949

PLUGGING
WELL SEC 32T-20R-13W
PAGE 4 LINE 32