

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15.009.01221.0000

API NUMBER 15- 1960

LEASE NAME McDonald

WELL NUMBER #1

4290 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 34 TWP. 20 RGE. 13 (E) or (W)

COUNTY Barton

Date Well Completed May 30, 1961

Plugging Commenced Jan. 25, 1994

Plugging Completed Jan. 25, 1994

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Riverside Petroleum Company

ADDRESS 314 East Santa Fe

PHONE # 816) 564-2575 OPERATORS LICENSE NO. 4540

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 20, 1994 (date)

by Dennis L. Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation K.C. Depth to Top 3276 Bottom 3557 T.D. 3557

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle				8/58	243	None
				5 1/2	3523	None

RECEIVED  
2-23-1994  
FEB 23 1994  
KANSAS CORPORATION COMMISSION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Run with tubing to 3340'. Spot 50 sks. cement with 300# hulls followed with 10 sxs. gel. Pull tubing to 1550'. Spot 40 sxs cement. Pull tubing to 725'. Spot 60 sxs. cement to circulate at surface. Pull tubing-squeeze casing with 15 sxs cement. Max. 300# S.P. 100# Hooked upto 8 5/8" S.P. Pressured to 500#.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. & Klima Well Serv License No. \_\_\_\_\_


Address P. O. Box 31, Russell, Ks. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Riverside Petroleum Company

STATE OF Kansas COUNTY OF Barton, ss.

Lloyd W. Bryant (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Lloyd W Bryant  
(Address) 314 Santa Fe Ellen, Ks.



SWORN TO before me this 22nd day of Feb, 1994  
Regina Marie Bullard  
Notary Public

My Commission Expires: 10-29-97