


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Flat

Location as "NE/CNW¹/₄SW¹/₄" or footage from lines Barton County, Sec. 34 Twp. 20 Rge. 13 (E) (W)
 Location as "NE/CNW¹/₄SW¹/₄" or footage from lines NW NW NW
 Lease Owner John Lindas Oil, Inc
 Lease Name Hiss Well No. 1
 Office Address Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed 12-22-51 19...
 Application for plugging filed 12-22-51 19...
 Application for plugging approved " 19...
 Plugging commenced 12-22-51 19...
 Plugging completed 12-23-51 19...
 Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production..... 19...
 Was permission obtained from the Conservation Division or its agents before plugging was commenced?..... Yes

Name of Conservation Agent who supervised plugging of this well C. S. Stough
 Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3625 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	224'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Set plug @ 220', 15 sacks cement, plug at 35', 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor John Lindas Oil, Inc
 Address 1316 Union National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Edward W. Wiens (employee of owner) or (owner/proprietor) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edward W. Wiens

1316 Union National Bank Building, Wichita, Kans
 (Address)

SUBSCRIBED AND SWORN to before me this 26th day of December, 19 51.

My commission expires My Commission Expires Nov. 5, 1955
Robert W. Nesbet
 Notary Public.

PLUGGING
 FILE SEC 34 T 20 R 13
 BOOK PAGE 133 LINE 19

DEC 27 1951
 CONSERVATION DIVISION
 WICHITA, KANSAS

15.009.01108.0000

DRILLING LOG

TO: Surray Oil Corporation,
Petroleum, Inc
Prairie States Oil Company
Edward G. Siebert
John D. McEwen
Justin Riley
John Lindas Oil, Inc.

LEASE: Hiss #1

County: Barton
Location: NW 24
Section: 34-20S-13W
Elevation: 1886' KB; 1884' DF

Rotary Total Depth: 3625'
Commenced: 12-11-51 Completed: 12-22-51
Casing: 8-5/8" @ 224' with 150 sacks of cement and 2 sacks of calcium chloride.

Contractor: John Lindas Oil, Inc. Rig #2
1316 Union National Bank Building
Wichita 2, Kansas.

FIGURES INDICATE BOTTOM OF FORMATIONS

0	to	10	Surface Dirt
10	to	175	Sand, Shale and Streaks
175	to	220	Shale
220	to	295	Shale and Sand
295	to	650	Red Bed and Shale
650	to	735	Red Bed and Sand
735	to	770	Anhydrite
770	to	960	Shale and Shells
960	to	985	Sand and Red Bed
985	to	1340	Salt, Shale and Red Bed
1340	to	1585	Shale and Shells
1585	to	1740	Lime
1740	to	2395	Lime and Shale
2395	to	2550	Shale and Shells
2550	to	2695	Lime and Shale
2695	to	2795	Shale and Lime
2795	to	2805	Lime
2805	to	2930	Broken Lime
2930	to	3110	Lime
3110	to	3285	Lime and Shale
3285	to	3365	Lime
3365	to	3435	Broken Lime
3435	to	3580	Lime
3580	to	3625	T. D. Lime

STATE OF KANSAS
DECEMBER 28 1951
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above statement and log is a true and correct record of the well drilled by John Lindas Oil, Inc. at the location above described.

Edward W. Wiens

Subscribed and sworn to before me, this 27th day of December, 1951.

Rich. W. Nesbet

My Commission Expires Nov: 5, 1955

PLUGGING
NOV 30 1951
BOOK PAGE 132 OF 19