


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barton County. Sec. 34 Twp. 20S Rge. (E) 13 (W)  
Location as "NE/CNW/SW" or footage from lines NE NW SE  
Lease Owner Circle Oil Company, Inc.  
Lease Name SHARP Well No. 1  
Office Address 500 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 27, 1966  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced August 27, 1966  
Plugging completed August 27, 1966  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Archie Elving)

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3652 Feet  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	266'	8-5/8"	8/22/66	-----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy Mud from Total Depth to 240 Feet;  
Hull & HOWCO Plug with 25 sacks cement  
thru the drill pipe; Mud to 40 feet,  
1/2 Sack Hulls and Plug bridged with  
Kelly; 10 sacks cement to base of  
cellar; 2 sacks in rat hole.  
Job completed at 1:45 P.M.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co., Inc.  
Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wayne W. Kahmeyer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer  
500 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 19 66

My commission expires November 26, 1966

Louise K. Whitted  
Louise K. Whitted - Notary Public.

DRILLERS LOGSHARP NO. 1

CASING RECORD:	COMPANY: Circle Oil Co.	DESCRIPTION:
8-5/8" @ 266'	CONTRACTOR: Sage Drilling Co.	NE NW SE
w/225 sax cement	COMMENCED: August 22, 1966	Sec. 34-20S-13W
TOTAL DEPTH:	COMPLETED: August 27, 1966	Barton County, Kansas
3562'		Elevation: 1880KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	110	
Clay & Shale	110	125	
Hard Sand	125	155	
Shale & Shells	155	267	
Red Bed	267	715	
Anhydrite	715	740	
Shale	740	810	
Shale & Sandy Lime	810	1590	
Lime & Shale	1590	3090	
Shale & Lime	3090	3365	
Lime	3365	3562	

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 2 1966  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING COMPANY, INC.

By Wayne W. Kahmeyer  
Wayne W. Kahmeyer

Subscribed and sworn to before me this 31st day of August, 1966.

Louise K. Whitted  
Louise K. Whitted - Notary Public

My commission expires:  
November 26, 1966.