


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barton County, Sec. 34 Twp. 20S Rge. 13W (E) (W)

Location as "NE/CNW%SW%" or footage from lines NW%SE%SE NW SW SE

Lease Owner Alpine Oil & Royalty Co., Inc.

Lease Name Fannie Sharp Well No. xxx8 1-C

Office Address 800 Bitting Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed October 27, 1961 19

Application for plugging filed October 27, 1961 19

Application for plugging approved October 27, 1961 19

Plugging commenced October 27, 1961 19

Plugging completed: October 27, 1961 19

Reason for abandonment of well or producing formation non-productive in commercial quantities

If a producing well is abandoned, date of last production \_\_\_\_\_ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3615 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT-IN	PULLED OUT
				8 5/8"	139	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud from total depth - 3615 feet to 139 feet. Plug of hulls and Halliburton plug 125 sacks cement through drill pipe, mud up to 40 feet; another plug and 10 sacks of cement

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 2 1961  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Quaker Drilling Co., Inc.  
Address 800 Bitting Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul  
800 Bitting Building, Wichita, Ks. (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of November, 19 61

My commission expires August 10, 1965 Reignier M. Murrell Notary Public.

WELL LOG

ALPINE OIL &amp; ROYALTY CO., INC.

Commenced: 10-19-61

Contractor: Quaker Drilling Co., Inc.

Completed: 10-27-61

Fannie Sharp No. 1-C  
NW SW SE Sec. 34-20S-13W  
Barton County, Kansas

Elevation: 1885 KB

Production: D. &amp; A.

## Casing Record:

Set 8 5/8 inch casing at 139 feet with 250 sacks cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil	25	Heebner	3140 -1255
Gravel	122	Brown Lime	3260 -1375
Hard Sand	144	Lansing	3277 -1392
Sand, Shale and Red Bed	605	Base of Kansas City	3495 -1611
Shale	750	Conglomerate	3503 -1618
Anhydrite	765	Rotary Total	
Shale	1300	Depth	3615 -1730
Shale and Shells	1560		
Lime and Shale	1625		
Sandy Lime and Shale	1755		
Shale and Lime	2030		
Shale and Shells	2330		
Shale	2535		
Shale and Lime	3160		
Lime	3180		
Shale	3260		
Lime	3495		
Shale and Chert	3615		

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 2 1961  
CONSERVATION DIVISION  
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the NW SW SE Sec. 34-20S-13W, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: Thomas M. McCaul  
Thomas M. McCaul, President

SUBSCRIBED AND SWORN TO before me a Notary Public this 30th day of October, 1961.

Virginia Mundell  
Virginia Mundell, Notary Public

My Commission Expires:  
August 10, 1965