


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec. 15 Twp. 30S Rge. (E) 16 (W)

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines C SW  
Lease Owner Pickrell Drilling Company  
Lease Name Robbins-Gallup 15 Well No. \_\_\_\_\_  
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 18, 1961  
Application for plugging filed September 18, 1961  
Application for plugging approved September 18, 1961  
Plugging commenced September 18, 1961  
Plugging completed September 18, 1961  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Fred W. Hampel, Pretty Prairie, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4775 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT-IN	PULLED OUT
				8 5/8"	285'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 270'. Set Plug. Cemented with 20 sacks cement. Heavy mud to 35'. Set Plug. Cemented with 10 sacks cement to bottom of cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 26 1961  
2-26-61  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
C. W. Sebitts (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) C. W. Sebitts, Partner  
705 Fourth National Bank Bldg., Wichita, Ks. (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of September, 19 61  
My commission expires September 24, 1962  
Maxine Johnson  
Maxine Johnson Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Bldg.  
Wichita 2, Kansas  
LOCATION: ROBBINS-GALLUP 15 - C SW, Sec. 15-30S-16W,  
Kiowa County, Kansas

Rotary Drilling Commenced 9/2/61  
Rotary Drilling Completed 9/18/61

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: 285' (6 jts.) 8 5/8" 20# Surface Casing with 170 sacks cement.  
Circulated. No oil string run. D & A

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

60'	Clay & Sand	<u>Circulated for Samples</u>	4685'
100'	Red Bed		4741'
710'	Red Rock & Shale		4746'
1765'	Shale & Shells		4755'
2050'	Shale, Shells & Limey		4760'
2765'	Lime		4765'
3390'	Lime & Shale		4775'
3650'	Chalky Lime		
3961'	Lime	<u>Slope Test</u>	
4159'	Lime & Shale	500'	0°
4464'	Lime	1500'	0°
4670'	Lime & Shale	2000'	0°
4676'	Shale	3000'	0°
4741'	Mississippi	4000'	0
4755'	Sand & Dolomite	<u>S. L. M.</u>	
4775'	Viola R.T.D.	1000'	
		25000'	
		3500'	
		4500'	

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 26 1961  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.

On this 22nd day of September, 1961, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: September 24, 1962

Maxine Johnson  
Maxine Johnson Notary Public