

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-097-20175-0000

API NUMBER 9-13-73

LEASE NAME Clinton Dean

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

330 Ft. from S Section Line

990 Ft. from E Section Line

LEASE OPERATOR J. Mark Richardson

SEC. 4 TWP. 30 RGE. 19 (X) or (W)

ADDRESS 640 Century Plaza Bldg., Wichita, Kansas 67202

COUNTY Kiowa

PHONE# (316) 262-3192 OPERATORS LICENSE NO. 5414

Date Well Completed 9-13-73

Character of Well Oil

Plugging Commenced 12-7-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-28-88

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 5064 Bottom -2764 T.D. 5180

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	682	0
				4 1/2	5181	2408

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sand off 4 1/2 Casing to 4700 ft.; dump ball 4 sx cement; pull 2408 ft 4 1/2 Casing; pumped 3 sx hulls; 10 sx gel; 50 sx 60/40 cement; 10 sx gel; 1 sx hull; 8 5/8 plug; 125 sx 60/40 sx cement - by B.J. Titan

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J. Mark Richardson, dba Greensburg Well Service License No. 5414

Address J. Mark Richardson; dba Greensburg Well Service; 640 Century Plaza Bldg., Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

J. Mark Richardson ~~XXXXXXXXXXXXXXXXXXXX~~ (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J. Mark Richardson

(Address) 640 Century Plaza Bldg. Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 9th day of February, 19 88

JUDY L. McMinn
State of Kansas
My Appt. Exp. 10-20-88

Judy L. McMinn
Notary Public
STATE CORPORATION COMMISSION

My Commission Expires _____

FEB 11 1988
2-11-88
Form CP-4
Revised 08-84
CONSERVATION DIVISION
Wichita, Kansas

