

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-21, 143-0000

LEASE NAME Parkin "B"

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 5 TWP. 30 RGE. 19 or (W)

LEASE OPERATOR Vincent Oil Corporation

ADDRESS 125 N. Market - Suite 1110, Wichita, Kansas 67202

COUNTY Kiowa

PHONE# (316) 262-3573 OPERATORS LICENSE NO. 5004

Date Well Completed 6-3-85

Character of Well D&A

Plugging Commenced 6-4-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-4-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	575	8 5/8"	5-25-85	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plug well with 175 sxs 60/40 poz, 2% gel, 3% cc as follows: 1230'-50' sxs; 610'-40' sxs; 510'-50' sxs; 40'-10' sxs with solid bridge; rathole-15 sxs; mousehole-10 sxs. Job by BJ-Titan Services. Plug down at 11:30 a.m. on 6-4-85

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Arnie Little

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Arnie Little


(Address) P. O. Box 329, Pratt, Kansas 67124



SUBSCRIBED AND SWORN TO before me this 12th day of June, 1985

Mary L. Tjaden
Notary Public

My Commission Expires: 3/22/88



- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

Oilfield Services, Inc.

DRILLER'S WELL LOG

Parkin "B" #1
 C. SW NW Sec. 5-30S-19W
 Kiowa County, Kansas
 Commenced: 5-24-85
 Completed: 6-4-85
 API #15-097-21,143
 Operator: Vincent Oil Corporation

Depth		Formation	Remarks
From	To		
0	690	Sand, Red Bed	Ran 12 joints (502.68') new, 23#, 8rd, 8 5/8" surface casing. Set at 515' with 175 sxs lite, 3% cc, 100 sxs Common, 2% gel, 3% cc. Cement did circulate. Job by BJ-Titan Services. Plug down at 8:30 a.m. on May 25, 1985.
690	1540	Red Bed	
1540	1780	Shale	
1780	5190	Lime, Shale T.D.	

RTD 5190'

Well was plugged with 175 sxs 60/40 poz, 2% gel, 3% cc as follows: 1230'-50 sxs, 610'-40 sxs; 510'-50 sxs; 40'-10 sxs with solid bridge; rathole-15 sxs; mousehole-10 sxs. Job by BJ-Titan Services. Complete at 11:30 a.m. on June 4, 1985. State Plugger was out of the Dodge City, Kansas office.

STATE OF KANSAS)
) ss
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

RECEIVED
 WHEATSTATE OILFIELD SERVICES CORPORATION COMMISSION
 JUN 14 1985
 ARNIE LITTLE, VICE-PRESIDENT CONSERVATION DIVISION
 Wichita, Kansas

NOTARY PUBLIC - State of Kansas
 MARY L. TJADEN
 My Appt. Exp. 3/22/88

Mary L. Tjaden
 NOTARY PUBLIC

My Commission Expires:
 3/22/88