


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

NORTH



Locate well correctly on above
Section Plat

Kiowa County, Sec. 12 Twp. 30S Rge. (E) 19 (W)
Location as "NE/CNWxSWx" or footage from lines. 150' S of C SW SW
Lease Owner Maurice L. Brown Trust
Lease Name Kane Well No. 1
Office Address 1515 Vickers/KSB&T Bldg., Wichita 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 21, 19 74
Application for plugging filed 19
Application for plugging approved June 21, 19 74
Plugging commenced June 21, 19 74
Plugging completed June 21, 19 74
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (G. R. Biberstein of Attica)

Name of Conservation Agent who supervised plugging of this well
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5115 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	625'	8-5/8"	625'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy Mud from Total Depth to 300 Feet,
35 sax Cement @ 300 Feet; Heavy Mud to
40 Feet, Plug & Bridge & 15 sax Cement
to Base of Cellar; 2 sax Cement in Rat
Hole. Job Completed @ 9:00 P.M.

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton
Address Pratt, Kansas 67124

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
T. M. McCaul, Jr. of Sage Drilling Co. (employee, contractor or owner or operator) of the above described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *T. M. McCaul, Jr.*

500 Bitting Bldg., Wichita, Kansas
(Address)

Subscribed and sworn to before me this 24th day of June, 1974.

Louise K. Whitted
Louise K. Whitted - Notary Public.

November 26, 1974



DRILLERS LOG

KANE NO. 1

CASING RECORD:	OPERATOR: Maurice L. Brown	DESCRIPTION:
8-5/8" set @ 625' w/1000 sax cement	CONTRACTOR: Sage Drilling Co.	150' S of C SW SW Sec. 12-30S-19W Kiowa County, Kans.
TOTAL DEPTH: 5115'	COMMENCED: June 3, 1974	ELEVATION: 2209KB
	COMPLETED: June 21, 1974	


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Shale	0	300	
Red Bed & Sand	300	466	
Red Bed	466	1000	
Shale	1000	1100	
Lime	1100	1574	
Lime & Shale	1574	2300	
Lime	2300	2610	
Lime & Shale	2610	2835	
Lime	2835	4085	
Lime & Shale	4085	4230	
Lime	4230	4426	
Lime & Shale	4426	4540	
Lime	4540	4810	
Lime & Shale	4810	4867	
Lime	4867	5115	D&A

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1974
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By T. M. McCaul, Jr.
T. M. McCaul, Jr.



Subscribed and sworn to before me this 24th day of June, 1974.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.