


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines KIOWA County, Sec. 12 Twp. 30S Rge. 19 (E) (W)
APP. SE SW
Lease Owner PETROLEUM, INC.
Lease Name KANE 'H' Well No. 1
Office Address R.R. #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed MAY 19 19 68
Application for plugging filed MAY 19 19 68
Application for plugging approved MAY 19 19 68
Plugging commenced MAY 19 19 68
Plugging completed MAY 19 19 68
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONE

If a producing well is abandoned, date of last production NONE 19 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELYING
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5105' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	844'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

HEAVY MUD TO 240', FOLLOWED BY WOODEN PLUG, 1/2 SACK HULLS, 25 SACKS CEMENT, MUD TO 40', FOLLOWED BY WOODEN PLUG, 1/2 SACK HULLS AND 10 SACKS CEMENT TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address R.R. #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.

MONTE CHADD (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.

(Signature) [Signature]
R.R. #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 21 day of MAY, 19 68

My commission expires MAY 28, 1969 [Signature] Notary Public.

WELL LOG

COMPANY Petroleum, Inc.

SEC. 12 T. 30S R. 19W

FARM Kane

NO. H-1

LOC. App SE SW


TOTAL DEPTH 5105'

COUNTY Kiowa, Kansas

COMM. 5-4-68

COMP. 5-19-68

CONTRACTOR Garvey Drilling Company



CASING

8 5/8" @ 844' w/550 SX

ELEVATION 2217' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- .250' Red Bed & Shale
- 306' Red Bed
- 343' Sand
- 603' Anhydrite
- .975' Red Bed
- 2100' Shale
- .2560' Lime & Shale
- .2849' Lime
- .4330' Lime & Shale
- .4408' Lime
- .4553' Lime & Shale
- .4705' Lime
- .4770' Lime & Shale
- .4827' Lime
- .4873' Lime & Shale
- .4897' Lime
- .5030' Lime & Shale
- .5045' Cherty Lime
- .5075' Lime & Shale
- .5105' Cherty Lime
- .5105' RTD

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 23 1968
 CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas

County of Barton

} ss

I, James R. Rodgers of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Kane H-1 well.

James R. Rodgers

Subscribed and sworn to before me this 20th day of May 1968

My Commission Expires: November 5th, 1969

Richard A. Boop
NOTARY PUBLIC