

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wich/36, Kansas

Ness County. Sec. 36 Twp. 20 Rge. 21 (E) (W)

Location as "NE/CNW/SE/SW" or footage from lines C NW SW

Lease Owner Donald C. Slawson

Lease Name Wells Well No. B-#1

Office Address 408 One-Twenty Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-21-65 19

Application for plugging filed 8-21-65 19

Application for plugging approved 8-21-65 19


Plugging commenced 8-21-65 19

Plugging completed 8-21-65 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4460 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 464' | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

RECEIVED
STATE CORPORATION COMMISSION

8-30-65

AUG 30 1965

Mud to 460' plug 20 sks. cement
Mud to 240' plug 20 sks. cement
Mud to 40' plug 1/2 sk. hulls 10 sks. cement
3 sks. in rathole

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of August, 1965

My commission expires October 19, 1965

Notary Public.



DRILLER'S LOG

COMPANY: Donald C. Slawson
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: WELLS B-#1
 LOCATION: C NW SW Sec. 36-20-21
 NESS COUNTY, KANSAS
 COMMENCED: 8-11-65
 COMPLETED: 8-21-65

| | | |
|------|-------------|---------------------------|
| 0 | 30 | Surface soil, clay |
| 30 | 195 | Surface clay, sand |
| 195 | 240 | Sand |
| 240 | 464 | Blue Shale |
| 464 | 850 | Shale & Redbed |
| 850 | 1025 | Dakota Sand |
| 1025 | 1390 | Shale & Redbed |
| 1390 | 1430 | Anhydrite |
| 1430 | 2100 | Shale & Shells |
| 2100 | 2255 | Shale & Lime |
| 2255 | 2600 | Lime & Shale |
| 2600 | 3040 | Shale & Lime |
| 3040 | 3905 | Lime & Shale |
| 3905 | 4400 | Lime |
| 4400 | 4455 | Lime & Chert |
| 4455 | 4460 | Lime |
| | <u>4460</u> | <u>RTD. - D. & A.</u> |

RECEIVED
 STATE CORPORATION COMMISSION

AUG 30 1965

CONSERVATION DIVISION
 Wichita, Kansas

8 5/8" used surface casing @ 464' with 375 sacks Common 2% cc

I, Leslie Kite, do hereby certify that the above and fore-going is a true and correct copy of the log of the Wells B-#1 located C NW SW of Section 36, Township 20, Range 21, Ness County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 27th day of August, 1965.

Emma M. Benoit

Emma M. Benoit

My Commission Expires:
 October 19, 1968

