


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 36 Twp. 20S Rge. 21W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C NW NE
Lease Owner Pickrell Drilling Company
Lease Name Nelson Well No. B-2
Office Address 205 Litwin Bldg. 110 N. Market Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 8-17-81 19____
Plugging completed 8-28-81 19____
Reason for abandonment of well or producing formation _____

Depleted
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4405'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	261'	none
				5-1/2"	4401'	2696'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in on location, ran sand to 4400' and set 5 sacks cement. Took stretch, shot casing @3206', 3015', and 2791', and 2695'. Pulled 86 joints pipe. Plugged well with 22 sacks gel, 5 sacks hulls, 8-5/8" plug, 140 sacks 50/50 pos, 4% gel, 3% cc. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
R. Darrell Kelso
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 19 81



My commission expires _____

RECEIVED
STATE CORPORATION COMMISSION

SEP - 2 1981

9-2-81

CONSERVATION DIVISION
Wichita, Kansas

BAKER OIL TOOLS, INC.

SERVING THE WORLD

DATE 5-28-81 WELL NO. 2 LEASE Nelson B FIELD Steffen

— 261 Base $8\frac{7}{8}$ " w/160 Sx

— 3160 Probable Collapsed Casing

— 3250 ESTIMATED Top of Cement

RECEIVED
STATE CORPORATION COMMISSION

JUN - 4 1981

CONSERVATION DIVISION
Wichita, Kansas

— 4401 Base $5\frac{1}{2}$ " 14.0 #3-55 w/135 Sx 50-50 Poz plus 35 Sx Cement

— 4405 LTD



BRIDGE PLUG



PACKER



CENTRALIZER



SCRATCHER



BASKET



PERFORATION

Approved
WLB 2-20-69

15.135.20225.0000

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita, Kansas 67202

Rotary Drilling Commenced 1-7-69
Rotary Drilling Completed 1-15-69

LOCATION: Nelson "B" No. 2
C NW NE Sec. 36-20S-21W
Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Ran 261.38' (14 jts.) used 28# 8 5/8" surface casing set at 261' KB and cemented with 160 sacks cement. Completed 3:45 PM, Jan. 7, 1969. Circulated.
Ran 4415.93' (140 jts.) 5 1/2" OD 14# casing set at 4401' KB (4' off bottom) and cemented with 135 sacks 50-50 Pozmix, 4% gel followed by 35 sacks common cement. Circulated. Completed 11:15 PM, Jan. 15, 1969

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

70	Post Rock	C. F. S.
261	Shale & Shells	4343'
600	Shale	4390'
845	Red Bed & Shale	4405'
1055	Sand	
1200	Shale & Sand Streaks	
1416	Shale	
1453	Anhydrite	Slope Tests
2364	Shale	2500'
2500	Shale & Lime	3000'
2630	Lime	3500'
2750	Lime & Shale	4000'
3150	Shale & Lime	
3410	Shale	
3700	Shale & Lime	
4245	Lime & Shale	S. L. M.
4305	Lime	4026'
4400	Lime & Shale	
4405	Mississippi, RTD	

RECEIVED
STATE CORPORATION COMMISSION
JUN - 4 1969
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

_____ day of February, 1969, before me the undersigned, a Notary Public, in and for the County of Sedgwick, State of Kansas, aforesaid, personally appeared C. W. Sebitts, to me known to be the person whose name is subscribed to the foregoing instrument as its free and voluntary act and deed, and as the free and lawful agent of such company, for the uses and purposes therein set forth. I and seal of office the day and year last above written.



My commission expires: May 10, 1970

[Signature]
Notary Public
L. M. Whiting