


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 28 Twp. 20S Rge. 20W ~~E/W~~
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SW SW

Lease Owner K & E Petroleum, Inc.
Lease Name Hagerman Well No. 1
Office Address 816 Union Center, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed November 14 1980
Application for plugging filed November 10 1980
Application for plugging approved November 10 1980
Plugging commenced November 10 1980
Plugging completed November 14 1980
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Depth to top Bottom Total Depth of Well 4340
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface hole	shale	surface	359	8-5/8	355	none
	Cemented with 275 sx common, 2% gel, 3% cc Plug down at 11:15 P.M. 11-4-80 by Sun.					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged as follows:

70 sx @ 680'

25 sx @ 270'

10 sx, plug & bridge @ 40'

5 sx in rat hole

Plug down at 3 a.m. 11-11-80; (used 50-50 poz, 4% gel) by Sun.

State Plugger Marion Schmidt.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Husky Drilling Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK
Jon T. Williams, Jr. (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

200 E. First, Suite 500, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of November, 1980

Geraldine Stewart
Geraldine Stewart Notary Public.

My commission expires January 12, 1981



15.145.20721.0000



200 East First, Suite 500
~~800 Boring Blvd~~
Wichita, Kansas 67202
Phone 316 - 263-7904
Mobile Phone 316 - 793-7859 Unit 7070

November 14, 1980

WELL LOG-----Hagerman No. 1
(Located: C SW SW of Sec. 28-20S-20W, Pawnee Co., Kansas)

OWNER: K & E Petroleum, Inc.
ROTARY CONTRACTOR: Husky Drilling Co., Inc.

COMMENCED: ~~October~~ ^{November} 4, 1980
COMPLETED: ~~October~~ ^{November} 11, 1980

Rotary Total Depth: 4340'

LOG

0 - 125	Soil, sand & shale
125 - 165	Sand
165 - 359	Sand & shale
359 - 765	Shale, sand & hard sand
765 - 960	Sand
960 - 1326	Shale & RedBed
1326 - 1356	Anhydrite
1356 - 3920	Shale & lime
3920 - 4300	Lime
4300 - 4310	Lime & shale
4310 - 4340	Lime

CASING RECORD

Ran 8 jts., used 24#, 8-5/8" casing, tallied 348.61' set @ 355 KB w/275 sx common, 2% gel, 3% cc Plug down at 11:15 p.m. 11-4-80 by Sun Cementing (cement did circ.)

Plugged & Abandoned 11-11-80.

I certify the above to be a true and correct copy of the driller's log to the best of my knowledge and belief.

HUSKY DRILLING CO., INC.

By [Signature]
Jon T. Williams, Jr., President

NOV 17 1980

CONSERVATION DIVISION
Wichita, Kansas