

LEASE NAME Stecklein

WELL NUMBER #1

1650 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 7 TWP. 20S RGE. 23W ~~23E~~ or (W)

COUNTY Ness

Date Well Completed 5/10/90

Plugging Commenced 8/1/00

Plugging Completed 8/1/00

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR WHITETAIL CRUDE, INC

ADDRESS P O Box 544, Ness City, KS 67560-0544

PHONE (785) 798-3641 OPERATORS LICENSE NO. 31627

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/20/00 (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippi Depth to Top 4423 Bottom 4433 T.D. 4433

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	779.5	-0-
				5 1/2	4423	1760

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section.  
 Plug bottom off with sand & 4 sks cement w/dump bailer. Shot casing off @ 1760', pumped

50 sks @ 1600'. Pulled pipe, pumped 50 sks @ 800', pulled pipe, pumped 40 sks @ 250', pulled pipe, pumped 10 sks to top off.

Name of Plugging Contractor Swift Services, Inc

Address P O Box 466, Ness City, KS 67560

RECEIVED  
 STATE CORPORATION COMMISSION


AUG 18 2000

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Whitetail Crude, Inc

STATE OF Kansas COUNTY OF Ness, ss. Wichita, Kansas

CONSERVATION DIVISION

Mike J. Fritzler, President of Whitetail Crude, Inc (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.



(Signature) Mike J. Fritzler

(Address) Mike J. Fritzler, President  
 P O Box 544, Ness City, KS 67560-0544

SUBSCRIBED AND SWORN TO before me this 11th day of August XX 2000

Debra Kerr  
 Notary Public

My Commission Expires: 4/20/2001

USE ONLY ONE SIDE OF EACH FORM