


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



NESS County, Sec. 7 Twp. 20 Rge. (E) 23(W)
Location nr "NE/CNWKSWK" or footage from lines SW NE
Lease Owner DANE G HANSEN TRUST
Lease Name MINER Well No. 1
Office Address LOGAN, KANSAS 67646
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed JUNE 5 19 74
Application for plugging filed JUNE 5 19 74
Application for plugging approved JUNE 5 19 74
Plugging commenced JUNE 5 19 74
Plugging completed JUNE 5 19 74
Reason for abandonment of well or producing formation
TOO LOWE STRUCTURALLY

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well LEO F MASSEY
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2326 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	371.81'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED WITH HEAVY MUD TO 600'. SET PLUG.
PUT IN 70 SACKS CEMENT. FILLED WITH HEAVY
MUD TO 240'. SET PLUG. PUT IN 20 SACKS
CEMENT. FILLED WITH HEAVY MUD TO 40'.
SET PLUG. FILLED TO TOP WITH 1 SACK HULLS
AND 10 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1974
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor C-G DRILLING CO.
Address 1107 UNION NATIONAL BUILDING, WICHITA, KANSAS 67202

STATE OF KANSAS COUNTY OF SEDGWICK
JAY H. GALLOWAY (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay H. Galloway
1107 Union National Building

Sworn to before me this 11th day of June 19 74



Phyllis Buchanan
Notary Public.

KANSAS DRILLERS LOG

S. 7 T. 20 R. 23 ^E/_W

API No. 15 — 135 — 20814-0000
County Number

Loc. SW NE

County NESS

Operator
DANE G HANSEN TRUST

Address
LOGAN, KANSAS 67646


Well No. 1 Lease Name
MINER

Footage Location
660 feet from ~~XX~~ (S) line 660 feet from ~~XX~~ (W) line

Principal Contractor **C-G DRILLING CO** Geologist **J E JESPERSEN**

Spud Date **MAY 24, 1974** Total Depth **4460** P.B.T.D.

Date Completed **JUNE 5, 1974** Oil Purchaser



Locate well correctly

Elev.: Gr. _____

DF 2326 KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8	20#	371.8'	Common	200	2% Gel + 3% C C

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

RECEIVED
 STATE CORPORATION COMMISSION
JUN 21 1974
 CONSERVATION DIVISION
 Wichita, Kansas

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS Oil _____ bbls. Gas _____ MCF Water _____ bbls. Gas-oil ratio _____ CFPB	Producing interval (s)
Disposition of gas (vented, used on lease or sold)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meadway (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **DANE G HANSEN TRUST** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: **DRY HOLE**

Well No. **1** Lease Name **MINER**

S **7** T **20** R **23** E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
SHALE & SAND	0	970		
RED BED	970	1085		
SHALE & SAND	1085	1485		
SHALE	1485	1607		
ANHYDRITE	1607	1636		
SHALE	1636	1725		
SHALE & SHELLS	1725	2305		
SHALE	2305	2500		
LIME & SHALE	2500	3840		
LIME	3840	4460		
RTD		4460		
DST #1 4420'-4441' OPEN 30 SI 30 OPEN 30 SI 30 REC 10' MUD IBHP 45# FBHP 36# IFP 18# FFP 27#				
DST #2 4420'-4460' MISRUM				
DST #3 4401'-4460' OPEN 30 SI 30 OPEN 60 PLUGGED TOOL - REC 125' OSM				
DST #4 4401'-4460' OPEN 30 SI 30 OPEN 60 SI 30 REC 65' MUD W/SHOW IBHP 891# FBHP 749#, IFP 23# FFP 89#				

RECEIVED
STATE DEPARTMENT OF MINES
MONTANA
JUN 13 1974

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

C-G DRILLING CO.
Phyllis Buchanan
 Phyllis Buchanan Signature
 Office Manager
 Title
 June 13, 1974
 Date