

WELL PLUGGING RECORD

NORTHEAST

Locate well correctly on above
Section Plat

McPherson County, Sec. 10 Twp. 20S Rge. (E) 3 (W)
Location as "NE/CNW¼SW¼" or footage from lines NW SE SW
Lease Owner Westgate-Greenland Oil Company, et al
Lease Name Mugler Well No. 1
Office Address 1022 Union National Bank Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed August 8, 1949 19
Application for plugging filed August 9, 1949 (verbally) 19
Application for plugging approved August 10, 1949 (written) 19
Plugging commenced August 8, 1949 19
Plugging completed August 8, 1949 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production..... 19.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?..... Yes.....

Name of Conservation Agent who supervised plugging of this well. Ruel Durkee
Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, fromfeet tofeet for each plug set.

filled hole with heavy mud from 3332 to 170 feet

Set plug and run 20 sacks cement from 170 feet

Filled with heavy mud to 30 feet and

capped with 5 sacks cement to bottom of cellar

RECEIVED

AUG 19 1949

8-19-49

STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Westgate-Greenland Oil Company

Address ~~4788 Broadway, Kansas~~ 1022 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas COUNTY OF Sedgwick

G. E. Bitler

(employee of owner) or ~~(owner or operator)~~ of the above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

1022 Union National Bank Building
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of August 1949

SUBSCRIBED AND SWORN to before me this 17th day of August 1949

My commission expires May 25, 1953

Notary Public

22-5133-S

9-48-10M

PLUGGING
FILE SEC 10 T 70 R 32
BOOK PAGE 108 LINE 40

COMPANY: Westgate Greenland Oil Company
 CONTRACTOR: Jackson Drilling Corporation
 FARM: Mugler #1
 LOCATION: NW SE SW Section 10-20-3W
 McPherson County, Kansas
 ELEVATION: 1485
 COMMENCED: July 28, 1949
 COMPLETED: August 8, 1949

0	to	35	Clay & sand
35	to	100	Shale - shells
100	to	124	Sand
124	to	172	Red Bed shale shells
172	to	230	Shale & shells
230	to	250	Red bed
250	to	480	Shale & shells
480	to	780	Lime & shale
780	to	810	Shale
810	to	825	Sand
825	to	955	Lime & shale
955	to	1025	Lime
1025	to	1630	Shale & shells
1630	to	1915	Shale & lime
1915	to	2090	Lime & shale
2090	to	2215	Lime
2215	to	2485	Lime & shale
2485	to	2785	Lime
2785	to	2864	Lime & shale
2864	to	2892	Lime
2892	to	3100	Lime & shale
3100	to	3332	Mississippi
		3332 T.D.	

8 5/8" - 32# casing set at 170 feet - cemented with 160 sacks cement & 1 sack calcium chloride

Tops - Lansing 2485
 Mississippi 3145

Dry and abandoned

Measurements taken from top of derrick floor

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the Mugler #1, Section 10-20-3W, McPherson County, Kansas, as reflected by files of the Jackson Drilling Corporation.


 Clare A. Stewart

Subscribed and sworn before me, a Notary Public, within and for Johnson County, Kansas this 16th day of August, 1949

AUG 19 1949

STATE CORPORATION
 COMMISSION

Dorothy J. Wilson

My Commission expires on November 30, 1950

KANSAS

