

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-097-20888

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Falcon Exploration Inc.

Complete Address 1531 KSB & T Bldg, Suite 1531 Wichita, Kansas 67202

Lease Name Wells Well No. 1

Location C-SW-NW Sec. 6 Twp. 30 Rge. 19 (East)(West)

County Nowata Total Depth 5200'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Santa Lee Drilling Co.

Address Box 8447, 1346 N. Woodlawn, Wichita, Kansas 67208 License No. \_\_\_\_\_

Operation Completed: Hour: 2:45 P.M. Day: 10 Month: July Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

1st plug at 1280' with 50 sby of cement. 2nd plug at 540' with 30 sby of cement. 3rd plug 40' to 0' on solid bridge with 10 sby of cement. Then circulated 10 sby of cement in rat hole. They pumped the cement through drill pipe with hole full of heavy mud. The cement used was 50/50 Pass mix with 2% Cell & 3% CC. The plugging was accomplished by Allied Cementing

Amount of Surface Casing: 50' of 8 5/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I was on a job when this well was being plugged.

Signed: Paul A. Luthi  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
7-20-82  
JUL 20 1982

INVOICED  
DATE 7-22-82  
INV. NO. 702-4

169.00