

KANSAS

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JUL 27 1976

7-27-76

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Maurice L. Brown Co

Complete Address 1500 Vickers KSB&T Bldg Wichita, KS

Lease Name Kane Well No. 2

Location C NW/NW Sec. 12 Twp. 30 Rge. 19 (E) (W) W

County Kiowa Total Depth 5154

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Voth Casing Pulling Co Inc

Address 715 S A Arkansas City, KS License No. 684

Operation Completed: Hour 11:30 AM Day 24 Month 7 Year 1976

The above well was plugged as follows:

409 ft 8 5/8 surface cemented with 400 sacks. 5152 ft 5 1/2 long string
cemented with 300 sacks. Open hole. Sand to 5100 ft, 5 sacks cement
with bailer. Pulled 2330 ft 5 1/2. Set 10 ft rock bridge at 240 ft.
Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed [Signature]
Well Plugging Supervisor

DATE 7/29/76

INV. NO. 3515-4