

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-135-20-225.0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name PICKRELL DRILLING COMPANY

Complete Address 205 LITWIN BLDG. WICHITA, KANS.

Lease Name NELSON Well No. "B" #2

Location C-NW-NE Sec. 36 Twp. 20 Rge. 21 (East) (West)

County NESS Total Depth 4405 FT

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor HELSO CASING PULLING

Address BOX 176 CHASE, KANS. 67524 License No. RECEIVED

Operation Completed: Hour: 11:00 AM Day: 28th Month: AUG Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

STATE CORPORATION COMMISSION
AUG 30 1981
CONSERVATION DIVISION
Wichita, Kansas

8 5/8" - 261 FT SP. CUL w/ 160ST CNT. → 5 1/2" SET AT 4401 FT w/ 135ST CNT.
NO PLUG. BACK - OPENHOLE 5 FT → SAND BOTTOM TO 4350 FT w/ 5ST CNT.
SHOT 4 TIMES RECOVERED 2692 FT
ORDERED - 140ST 50/100 F22 MIX 4% GEL - 3% CACL. + 22ST GEL.
5ST HULL'S. + 8 5/8" PLUG. → PUMPED IN 8 5/8" WITH PUMP TRUCK.
PUT IN 4ST HULL'S. → 14ST GEL. → 1ST HULL'S. → 70ST CNT.
7ST GEL. → RELEASED PLUG. AND 70ST CNT.
MAX PRESSURE 1100 ^{LB}

8-31-81 AUG CEMENTED BY ALLOWED CNT.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Wichita, Kansas
Signed: Wesley Schmidt
Conservation Division Agent

DATE 9-25-81

INV. NO. 7449W