

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 10 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name D. G. Hansen Trust

Complete Address Box 187, Logan, Kansas

Lease Name Minor Well No. 1

Location SW NE Sec. 7 Twp. 20 Rge. (E) (W) <sup>23</sup>

County Ness Total Depth 4460'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor C & G Drilling

Address Wichita, Kansas License No.       

Operation Completed: Hour 10:30 A Day 5 Month 6 Year 1974

The above well was plugged as follows:

RTD 4460' 8 5/8 csg set at 371' cwc 200 sk. Cmt. Mat. 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *Leo Massey*  
Well Plugging Supervisor

INVOICED

DATE 6/11/74

INV. NO. 9282-W