

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 5 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Circle Oil Company, Inc.

Complete Address: 500 Bitting Bldg., Wichita, Kansas 67202

Lease Name Hiss Well No. # 1

Location NE NE NW Sec. 33 Twp. 20 Rge. 13 (E) (W) W

County Barton Total Depth 3637

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling Co.

Address: Great Bend, Kansas 67530 License No. # 49

Operation Completed: Hour 11:45AM Day 30 Month 8 Year 1967

The Above well was plugged as follows:

TD-3637' 8 5/8" 217' 5 1/2" 3634'

Sanded hole back to 3584' & dumped 4 sax cement with dump bailer. Pulled pipe.

Squeezed well with 20 sax mud & 85 sax cement with pump truck, cementing from

260' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don L. Lusk  
Well Plugging Supervisor

DATE 9/5/67

INV. NO. 6255-W