

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 101-14

LOCATION NE-SW-22W

SEC. 32 TWP. 20 RGE. 13-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Hartman

Operator Ben F. Braek Oil Co., Inc. Address #309 Brown Bldg. Wichita-Kans.

Field _____ County Barton

Total Depth 3552 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 142 ft. Circulated with cement
5/8 casing set at 3528 ft. - 100 sacks of cement. Plugged
back to 3500 ft with sand & chat. Dumped 5 sacks cement
at 3500 ft. Shot off & pulled the 5/8 casing - Pumped in
30 sacks of heavy sand Plug & 100 sacks of cement
filling hole from 300 ft to the surface with cement
Pumped in by Halliburton
Pipe Pulling, Inc. Plugging Contractors

PLUGGING
FILE SEC 32 T 20 R 13W
BOOK PAGE 101 LINE 14

RECEIVED
STATE CORPORATION COMMISSION

C. M. Stouck
District Conservation Agent
Date 5-21-53

5-23-1953