

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-20,951-0000

TECHNICIAN'S PLUGGING REPORT

C SE NW Sec. 14, T 30 S, R 16 W/E

PUB 3300 (5) 660 feet from N/S section line  
1980 feet from W/E section line

Operator License # 8691

Lease Name Isabella Wright Well # 1

Operator: S+G Drilling Co. Inc  
Name & Address: 927 Maple  
Duncan Oklahoma  
73533

County: KIOWA  
Well Total Depth 4735 feet 8153.89  
Conductor Pipe: Size 20" feet 74'  
Surface Casing: Size 10 3/4" feet 460

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Aldebaran Drilling Co. Inc License Number 5829

Address P.O. Box 18611 Wichita, Kansas 67207

Company to plug at: Hour: 6:00am Day: 12 Month: June Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Larry Harris

(company name) Aldebaran Drilling Co. Inc (phone)

were: To use 60/40 pozmix 2% gel 3% cc

1st plug @ 1380' w/50sx, 2nd plug @ 900'

w/50sx, 3rd plug @ 480' w/50sx, 4th plug

@ 40' w/solid Bridge Plug + 10sx, Circulate

10sx each in th pathole + mousehole

Signed Richard W. Lacy  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 8:30am Day: 12 Month: June Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered in above paragraph  
Sun pumped the cement

Remarks: Mr. Steve Durrant approved the plugging  
proposal

RECEIVED  
STATE CORPORATION COMMISSION

JUN 14 1983

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / did not) observe this plugging.

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 6-20-83

INV. NO. 4621-W

Signed Richard W. Lacy  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82