

1 030321

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,072-0000
SE NE NW , SEC. 1 , T 30 S, R 19 W/EK

4290 feet from S section line
3120 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5171

Lease Name Koger Well # 2
County Kiowa

Operator: TXO Production Corp.
Name &
Address 200 West Douglas, Suite 300
Wichita, KS 67202

Well Total Depth 5250 170.63 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 618

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Freeman Drilling, Inc. License Number 5106
Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 7:00 am Day: 3 Month: November Year: 19 84

Plugging proposal received from Rex Cravens
(company name) TXO (phone) 316-265-9441

were: _____ to fill hole with heavy mud and spot cement through drill pipe RECEIVED
STATE CORPORATION COMMISSION

1st plug at 1260' with 50 sx cement

2nd plug at 630' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement
CONSERVATION DIVISION
Wichita, Kansas

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Steve Belmont
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:30 am Day: 3 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1260' with 50 sx cement, 2nd plug at 630' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc
(If additional description is necessary, use BACK of this form.)

INVOICED

I (XXX / did not) observe this plugging.

DATE 11-19-84

Signed Steve Belmont
(TECHNICIAN)

INV. NO. 4817

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: October 26 1984
month day year

API Number IS- 097-21,072-0000

OPERATOR: License # 5171
Name TXO Production Corp.
Address 200 W. Douglas, Suite 300
City/State/Zip Wichita, KS 67202
Contact Person Gary Wurdeman
Phone 316-265-9441

SE NE NW Sec 1 Twp 30 S. Rge 19 East
(location) West
4290 Ft North from Southeast Corner of Section
3120 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5106
Name Freeman Drilling, Inc.
City/State Wichita, Ks

Nearest lease or unit boundary line 330 feet.
County Kiowa
Lease Name KOGER Well# 2
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 100 feet
Lowest usable water formation Unknown
Depth to Bottom of usable water 200 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 613 feet
Conductor pipe if any required 0 feet
Ground surface elevation TBD feet MSL
This Authorization Expires 4-22-85
Approved By 10-22-84 *J.C.*

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 5100 feet
Projected Formation at TD Miss Lime
Expected Producing Formations Miss Lime

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

10-19-84 Signature of Operator or Agent *Jerry W. Collins* Title District Engineer
mhc/4011E 10/22/84 Form C-1 4/84

RECEIVED
STATE CORPORATION COMMISSION
NOV 08 1984
CONSERVATION DIVISION
Wichita, Kansas